


Flexiscreen®

high grade building screen

Flexiscreen is proven to shield open buildings from inclement weather, contain dust and regulate temperature. There are **three Flexiscreen panel connection methods (seal types) to choose from**, enabling you to balance performance versus speed of delivery/install. Which seal type you choose is dependent on your project's specific requirements.



	Flexiscreen	Flexiscreen Rapid	Flexiscreen Fast
Seal type (panel connection method)	V-Overlap 	Zip 	Hook & Loop 
Use type	internal / external	external	internal
Weather protection	✓	✓	
Dust protection	✓	✓	✓
Site survey & drawing pack	✓		
Penetration seal	✓	✓	✓
Temporary works design package (in accordance to BS 5975)	✓		
Wind load calculations (in conjunction with TWD and in accordance to BS EN 1991-1-1)	✓	✓	
Air permeability guarantee	✓		
Heights up to	any height	12m	12m
Lead time to project start*	4-6 weeks	2-3 weeks	3-4 weeks

Watch our Flexiscreen videos ▶

Call us today to start your weather protection and dust containment planning...



*Project lead times are estimated from acceptance of order, and subject to our standard terms and conditions. Installation methods may vary depending on specific project requirements. This fact sheet is for illustrative purposes only and based on the latest information at the time of print. Westgate Global reserve the right to make changes at any time without notice. Flexiscreen® Rapid - patent pending: GB2513438.8

J229-WFD-PFS-FS-ST-021025 © Westgate Global Ltd